INSTALLATION INSTRUCTIONS

PERFORMANCE SCONCE 111, 113 AND 114

SPLICES (BY OTHERS)-

HANGER

BRACKET

J-BOX SCREW

SEALANT (BY OTHERS) -

MOUNTING BRACKET

OPTIONAL 1/4" MAX. DIA.-MOUNTING BOLT OR SCREW

(1 OF 4) (BY OTHERS)

IMPORTANTREAD ALL INSTRUCTIONS BEFORE PERFORMING ANY WORK.

BE SURE ALL POWER IS OFF PRIOR TO INSTALLING LUMINAIRE.

WARNING:LUMINAIRE MUST BE GROUNDED IN ACCORDANCE WITH APPROPRIATE CODES. FAILURE TO DO SO MAY RESULT IN SERIOUS INJURY.

STANDARD INSTALLATION

NOTE: MOUNTING BRACKET MAY
BE SECURED TO WALL WITH UP
TO 1/4" DIA. BOLTS OR SCREWS
(BY OTHERS).

STRUCTURAL MEMBERS MUST BE PRESENT IN WALL TO ACCEPT BOLTS OR SCREWS.


111,113 or 114 SHAPE

1. APPLY A BEAD OF SEALANT ON WALL AROUND SPLICE BOX OPENING AND AROUND HOLES USED FOR OPTIONAL MOUNTING BOLTS OR SCREWS.

WHEN USING A 4" OCTAGONAL BOX (SHOWN), FILL GAP BETWEEN WALL OPENING AND SPLICE BOX WITH SEALANT.

APPLY SEALANT TO THE TOP INSIDE CORNERS OF THE MOUNTING BRACKET.

- 2. PLACE MOUNTING BRACKET OVER SPLICE BOX AND SECURE WITH J-BOX SCREWS. FOR ADDITIONAL SECURITY, BOLTS OR SCREWS UP TO 1/4" DIAMETER MAY BE USED.
- 3.MAKE ELECTRICAL CONNECTIONS. FIXTURE LINE TO SUPPLY LINE, COMMON TO COMMON AND GROUND TO GROUND.



-SPLICE BOX (BY OTHERS)

MOUNTING PATTERN FOR OPTIONAL BOLTS

4" OCTAGONAL BOX (BY OTHERS)
SHOWN FOR REFERENCE

©2016 Philips Lighting Holding B.V. All Rights Reserved. www.philips.com/luminaires

443561012970/A817191 REV. B Page 1 of 2



INSTALLATION INSTRUCTIONS PERFORMANCE SCONCE 111, 113 AND 114

- 4. PLACE SPLICES AND EXCESS WIRE IN SPLICE BOX. CAREFULLY ENGAGE HANGER BRACKET TO MOUNTING BRACKET BEING CAREFUL NOT TO PINCH WIRES. ALLOW FIXTURE TO REST AGAINST WALL. TIGHTEN LOCKING SCREWS.
- 5. UNSCREW LENS FRAME SCREWS, OPEN FRAME, INSTALL LAMP, CLOSE AND SECURE FRAME BEING CAREFUL NOT TO OVER TIGHTEN THE SCREWS.